CHITALDRUG DISTRICT.

Dated 8th March 1919. 747

CONSTRUCTING COMPOUND WALL FOR THE TOWN HALL.

Notice is hereby given that sealed tenders will be received at the Office of the President, District Board, Chitaldrug District, up to 15th April 1919. An approximate estimate of the quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. The plans, detailed estimate and conditions may be seen at the President's Office at Chitaldrug between the hours of 12 noon to 5 P.M. on office days.

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the Town Hall compound wall, Chitaldrug" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the President, District Board, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the District Board President's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work	Quantity	Per
Earthwork excavation for foundation	157	C. yd.
Concrete for foundation	1,122	C. ft.
Burnt brick in mortar	5,809	"
Plastering with mortar	74	Sq.
Whitewashing 2 coats	8½	"
Colour washing	65	"
Coping over pillars with burnt brick in mortar with plaster	88	Each
Coping over compound wall	1,305	R. ft.
Gate portion—		
Earthwork excavation for foundation	9	C. yd.
Concrete for foundation	96	C. ft.
Burnt brick in mortar	368	"
Plastering with mortar	4½	Sq.
Whitewashing 2 coats	4	"
Colour washing	2	"
Providing ornamental coping over gate pillars	4	Each
Coping over pillars at ends of wings	4	"
Coping over wings	32	R. ft.
Providing ornamental iron gates including fixing, etc., complete	2	Each

M. ZAHIRUDDIN MECCI,
President, District Board.

THE BANK OF MYSORE, LIMITED, BANGALORE.

Dated 13th March 1919.

Notice is hereby given that the undersigned will receive sealed tenders up to the 15th April 1919, for the construction of Mysore Bank Buildings in Davangere Town, a plan of which is open for inspection at the Bank of Mysore, Ltd., Bangalore, during business hours. All other information will be furnished to the tenderer on personal application.

W. C. ROSE,
Manager.

PRIVATE ADVERTISEMENTS.

IN THE COURT OF THE SUB-JUDGE AT BANGALORE.

Miscellaneous Application No. 251 of 1918-19.

In the matter of the estate of S. Venkataramachar ... ... *Deceased.*

(1) S. V. Srinivasa Rao, (2) Rama Rao, (3) Lakshmana Rao, (4) Narayana Rao, (5) Krishna Rao, minors by next friend Bhagirathamma .. .. *Applicants.*